

Temporary Closure: New Build Construction Sites Guidance

New Build Construction Sites

The construction industry has been rapidly ramping up preparations to deal with the coronavirus. This could lead to some construction sites being minimally occupied e.g. safety critical trades may continue or, in the worst-case scenario, long term site shutdowns.

Where we insure a construction site and the existing site security measures remain fully resourced and in place, there is no need to advise Zurich if the site has switched to a skeleton staff operation however should your 24/7 security guarding is removed then, please contact Zurich in advance to seek advice.

For general construction sites, we would ask that you follow the below control measures.

Risk Control Measures

- **Combustible Materials & Waste:** All combustible building materials, waste and pallets to be removed from site or stored in locked steel containers.
- **Existing Site Security:** All current site security measures are to remain in place 24/7 e.g. access gates are locked, any scaffold alarms are set.
- **Security assessment:** Ahead of the site closing, complete a security risk assessment to consider the need for additional security measures e.g. scaffold alarms, regular security patrols, improve site hoarding and access gate security.
- **Valuable Equipment:** Remove or secure any valuable machinery, hired-in plant, building materials such as copper cabling.
- **Site safety:** Continue to comply with any legal or safety requirements including inspections e.g. checking the roof for any loose material that could be a hazard in stormy conditions. Please ensure that you comply with existing government guidance regarding vulnerable people and lone worker risk assessments. Consider the provisioning for alternative skilled personnel.
- **Site issues:** If you have experienced recent thefts, malicious damage or squatting issues please contact Zurich for guidance.
- **Site safety:** Complete a risk assessment to ensure the site is safe against trespassers e.g. access to scaffold platforms are removed or secured.
- **Escape of Water:** Please consider draining down and isolating any temporary or permanent water supplies to the building.

Complex Construction Sites:

- There is an expectation that we are notified of any material changes to complex and large construction sites.
- These will be large infrastructure, civil engineering or major construction sites
- We will be actively discussing with our customers the implications in the event the site is impacted by lockdowns caused by the coronavirus.
- If in doubt, please provide full details of the changes to Zurich and we will remotely review your construction project security and site arrangements via our in-house Risk Engineering team of specialists.



Temporary Construction Site Closure Checklist

Here is a short checklist that we have developed to help secure the building and to use as a reference point for regular checks during temporary closedown periods.

Site checks

Remove all combustible waste, building materials (or store securely), pallets and empty skips Yes No Date:

Flammable and pressurised gas cylinders are stored in a suitable external cage or preferably removed from site Yes No Date:

Daily site inspections are advised (minimum weekly on a risk assessed basis) Yes No Date:

Further site inspection requirements have been identified and put into place e.g. scaffold inspection, post-adverse weather site inspection Yes No Date:

Any existing manned guarding e.g. overnight, weekend or security patrols continue Yes No Date:

Non-essential building utilities, temporary or permanent, and equipment have been safety isolated. No charging left on. Yes No Date:

Any temporary or permanent fire alarms are operational, and any faults reported/rectified Yes No Date:

Valuable contents, hired-in plant or machinery have been removed from site or securely stored Yes No Date:

Site hoarding is complete and in good condition Yes No Date:

Building access is secured if possible e.g. ground floor access to cores are secured. Yes No Date:

External gates are adequately locked/secured Yes No Date:

Security intruder alarm and/or scaffold alarm is working correctly and activated whenever the building is secured including any remote signalling Yes No Date:

Security keyholder response is updated and adequately resourced Yes No Date:

External lighting is operational Yes No Date:

CCTV is operational with adequate lighting Yes No Date:

Any planned hot work activities are strictly delayed or switched to lower risk alternatives Yes No Date:

Hot work permit procedures strictly are adhered to Yes No Date:

Consider draining down and isolating any water pipes to avoid the risk of water leaks Yes No Date:

This guidance may change as the current situation changes, [please refer back here](#) for our position on policy cover.

Zurich Insurance plc Zurich Insurance plc, a public limited company incorporated in Ireland. Registration No. 13460. Registered Office: Zurich House, Ballsbridge Park, Dublin 4, Ireland. UK Branch registered in England and Wales Registration No. BR7985. UK Branch Head Office: The Zurich Centre, 3000 Parkway, Whiteley, Fareham, Hampshire PO15 7JZ. Zurich Insurance plc is authorised by the Central Bank of Ireland and authorised and subject to limited regulation by the Financial Conduct Authority. Details about the extent of our authorisation by the Financial Conduct Authority are available from us on request. Our FCA Firm Reference Number is 203093.

Communications may be monitored or recorded to improve our service and for security and regulatory purposes.

© Copyright – Zurich Insurance plc 2020. All rights reserved. Reproduction, adaptation, or translation without prior written permission is prohibited except as allowed under copyright laws.

